

Commercial and Operational Office

Office 1503, Fortune Executive Tower Jumeirah Lake Towers (JLT), Cluster T Dubai, United Arab Emirates Tel: + 971 48 920 940 info@vortexoffshore.com www.VortexOffshore.com

AHT - SUPPLY - DP2 - FIFI1 VORTEX VENTURE

10,760 BHP | 140 TBP



SPECIFICATIONS:

ANCHOR HANDLING & SUPPLY TUG, FIFI 1, DP-2

GENERAL:

Vessel Type: Anchor Handling Tug Supply Vessel DP2 Built 2009, Keppel Nantong Shipyard Co.,Ltd. Built:

IMO no: 9421192 Official no: 24017 5LQ03 Call Sign: Liberia Flag: Classification:

Class Notation: **★**CSA Tug/Offshore Supply Ship/Fire Fighting Ship 1;

Anchor Handling ★CSM AUT-0; DP-2; SCM

DIMENSIONS:

CAPACITIES:

Length Overall: 76.00 m Deck Strength: 10 T/m² 37.85 x 13.61mtrs Deck Size: 17.00 m Beam (Moulded): Clear Deck Area: 515 m² @1000T 7.60 m Depth (Moulded): Fuel Oil: 1056 m³ Draft (Moulded): 6.20 m Fresh Water: 485 m³ GRT: 2.943 T Drill Water: 1019 m³ NRT: 883 T Mud: 650 m³ Liquid Mud: Deadweight: 2700 T 650 m³ @ 6.2 m draft Brine: 214 m³ Base Oil: 215 m³ Dry Bulk: 260 m³

SPECIAL FEATURES:

Four main Engines deliver maximum fuel economy with excellent redundancy All thrusters are independently driven (no shaft generators)

Rig Chain Locker:

Chain Capacity:

Twin stern rollers

215 m³

3070 m

MACHINERY:

Main Engines: 4 x 2690 bhp; MAK 6M25 Main Generators: 3 x 601 kw; CAT C18 Harbour Generator: 1 x 425 kw; CAT C18 Emergency Generator: 1 x 99 kw; CAT 3506

Tunnel Bow Thruster 1: 1 x 632 kw x 8.5 tons Thrust Tunnel Bow Thruster 2: 1 x 632 kw x 8.5 tons Thrust Tunnel Stern Thruster: 1 x 632 kw x 8.5 tons Thrust Steering Gear: 2 x 45 degree

Propulsion: 2 x CPP with Fixed Nozzle

Rudders: Split, High Lift

PERFORMANCE:

Bollard Pull: 140 T Speed(max): 14 Kts Cruising speed: 12 Kts Speed(econ): 9 Kts

> Twin sharks jaws and twin tow pins

Superb machinery redundancy

The Vessel specifications are reviewed and new brochures printed at regular intervals. Every endeavour has been made to provide accurate information on this brochure; however, the vessel owners do not accept any liability for errors, omissions or misprints published.

Page | 1



Commercial and Operational Office

Office 1503, Fortune Executive Tower Jumeirah Lake Towers (JLT), Cluster T Dubai, United Arab Emirates Tel: + 971 48 920 940 info@vortexoffshore.com www.VortexOffshore.com

AHT - SUPPLY - DP2 - FIFI1 VORTEX VENTURE

10,760 BHP | 140 TBP

ANCHOR HANDLING & TOWING:

Line Pull: 350 T

Winch: Triple Drum SMATCO

Main Tow Wire:1000m x 64mm (max capacity 2976m x 76mm)Second Tow Wire:1200m x 76mm (max capacity 1524m x 76mm)Work Wire P:100 x 77mm (max capacity 1524m x 76mm)Spare wire 1:1000m x 64mm (max capacity 1500m x 76mm)Spare wire 2:1000m x 76mm (max capacity 1500m x 76mm)Braking Capacity:441 T (Remote control from aft control stand in

wheelhouse)

Towing Pin: 2 x twin hydraulic operated type SWL 400T Sharks Jaw: 2 x twin hydraulic operated type SWL 500T

Stern Roller: Split Roller 2.5 m each Ø and 5 m length w/ SWL 500T

NAVIGATION/ COMMUNICATION:

2 x SART

1 Navtex

1 EPIRB

2 x Radars ARPA

1 Doppler speed log

2 Master Gyro's with 5 repeaters

1 Magnetic Compass

1 GPS

1 Echo sounder

1 Set of GMDSS radio station system for Area 3. Including SSB, Inmarsat C, MF/HF,VHF with DSC etc.

3 x VHF GMDSS

Ship Security Alert System

1 x AIS

1 x Bridge Navigational Watch Alarm System

1 x VSAT Internet / Telephone System

ACCOMODATION:

Total:

42 Berths, Fully Air-Conditioned

6 x 1 berth cabins = 6 18 x 2 berth cabins = 36 1 x 2 berth cabins (hospital)

DISCHARGE RATES:

 Fuel Oil:
 $2 \times 200 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Fresh Water:
 $2 \times 200 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Drill Water:
 $2 \times 200 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Mud:
 $2 \times 75 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Brine:
 $2 \times 75 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Base Oil:
 $2 \times 150 \text{ m}^3/\text{hr}@90 \text{ m}$ head

 Slop Disc:
 $1 \times 5 \text{ m}^3/\text{hr}@45 \text{ m}$ head

Dry Bulk: 2 x 75 T/hr

FIREFIGHTING - FIFI CLASS 1:

FiFi System: with external drench system, full vessel

Fire Pump: $2 \times 1600 \text{ m}^3 / \text{hr}$

Monitors: 2 x 1200 m³ / hr (w/spray and remote control)

INTERNAL:

Emergency Fire Pump

CO² System in engine room, BT room, and ST room Fire Detection & Alarm System throughout vessel BA Recharging Compressor 75 ltr/min @ 200bar

SAFETY/LIFESAVING EQUIPMENT:

SOLAS Compliant

Rescue boat: 1 x 15 man FRC

DYNAMIC POSITIONING / JOYSTICK: DP2

DPS L3 NHS 6000

2 x DP Controller + Independent Joystick

2 x Wind Sensor

2 x Master Gyro

2 x DGPS

VMS System which includes Vessel Power Management

MISCELLANEOUS:

Rescue Zone: Port & Std side

Oily Water Separator: 1 x 1 m³/hr MARPOL standard

Sewerage Treatment Plant: $1 \times 42 \text{ men per day}$

Windlass: 9T @ 12 m/min for 40 mm Ø, Chain w/2 cable lifers,

2 warping drums & rope drum

Bow Anchors: High-holding type anchors 2x 2640 kg

Chains: 467 m x 40 mm Ø Grade

3 stud link chain p & s

Tugger Winches: $2 \times 10T @ 15m/mins$ Capstans: $2 \times 10T @ 15m/mins$

2 x Spray Booms

Deck Crane: 5T @ 15mtrs

The Vessel specifications are reviewed and new brochures printed at regular intervals. Every endeavour has been made to provide accurate information on this brochure; however, the vessel owners do not accept any liability for errors, omissions or misprints published.

Page | 2 Rev 2.1 Dt 07/01/25




Commercial and Operational Office

Office 1503, Fortune Executive Tower Jumeirah Lake Towers (JLT), Cluster T Dubai, United Arab Emirates Tel: + 971 48 920 940 info@vortexoffshore.com www.VortexOffshore.com

AHT - SUPPLY - DP2 - FIFI1 VORTEX VENTURE

10,760 BHP | 140 TBP



The Vessel specifications are reviewed and new brochures printed at regular intervals. Every endeavour has been made to provide accurate information on this brochure; however, the vessel owners do not accept any liability for errors, omissions or misprints published.

Page | 3 Rev 2.1 Dt 07/01/25